

ADDENDUM NO. ONE (1)
CITY OF HOSCHTON
2023 LMIG ROADWAY IMPROVEMENTS
RFP #003
EMI PROJECT NUMBER 21-009
ISSUED APRIL 5, 2023

The following items of the RFP are modified as part of this Addendum:

➤ Section VIII. Material, Cost, Hours, and Price – Bid Schedule

The Bid Schedule has been revised as follows:

1. Updated the quantity of Asphalt Patching – Full Depth for the City Cemetery Drives.

A revised Bid Schedule is attached.

Clarifications

The following are clarifications based on questions received.

1. **Regarding the cemetery patching, do you know approximately how large each area is and what the paving spec is to remedy each area?**

Response: There are three areas designated for patching. All three areas are on the drive connected to Cabin Drive and they have now been marked in the field. The approximate dimensions for the areas are 3'x3', 6'x10', and 4'x3'. To remedy each area, the existing pavement adjacent to these repair locations shall be sawcut and existing material removed as necessary to a depth of 2.0 inches below the top of the existing asphalt around the perimeter. Then place 2-inches of 12.5 mm Superpave at 110 lbs/sy/in in the repair areas.

2. **Does the City want the contractor to pulverize the existing asphalt in place to be used as additional stabilization in the road once mixed with the cement or completely remove the asphalt and discard prior to mixing?**

Response: The City wants the Contractor to pulverize the existing asphalt in place to be used as additional stabilization in the road once mixed with the cement. If any waste asphalt/GAB mixture is generated from the pulverization process, Contractor to coordinate with City for stockpiling at the City's wastewater treatment plant.

END OF ADDENDUM NO.1

Receipt of Addendum 1 is hereby acknowledged By: _____

Firm Name: _____

VII. MATERIAL COST, HOURS, AND PRICE

BID SCHEDULE						
Overall Project						
LINE NO.	GDOT ITEM	ITEM	QUANTITY	UNIT	UNIT AMOUNT	AMOUNT
0010	150-1000	Traffic Control	1	LS		
Bell Avenue from White Street to Hall Street						
0015	402-3103	Recycled Asphaltic Concrete 9.5 mm Superpave, Type II, GP 2 Only, Incl Bitum Matl & H Lime	180	TN		
0020	413-1000	Bituminous Tack Coat	340	GAL		
0025	415-5000	Asphaltic Concrete Open Graded Crack Relief Interlayer, GP 2 Only, Incl Bitum Matl & H Lime	125	TN		
0030	432-0210	Mill Asphaltic Concrete Pavement, 2 1/2 in. Depth	2,090	SY		
0035	653-1502	Thermoplastic Solid Traffic Stripe, 5 in, Yellow	1,755	LF		
0040	653-1704	Thermoplastic Solid Traffic Stripe, 24 in, White	36	LF		
0045	706-1003	Turf Establishment, TP C	0.12	AC		
Hall Street from Bell Avenue to Broad Street						
0050	301-2160	Soil-Cem Stab Base Crs, 8 in	945	SY		
0055	301-5000	Portland Cement	30	TN		
0060	402-3113	Recycled Asphaltic Concrete 12.5 mm Superpave, Gp 1 or 2, Incl Bitum Matl & H Lime	110	TN		
0065	413-1000	Bituminous Tack Coat	80	GAL		
0070	653-1704	Thermoplastic Solid Traffic Stripe, 24 in, White	18	LF		
0075	706-1003	Turf Establishment, TP C	0.07	AC		
See Next Page for Bid Schedule Continuation						

BID SCHEDULE

Mulberry Street from Bell Avenue to Broad Street

0080	301-2160	Soil-Cem Stab Base Crs, 8 in	970	SY		
0085	301-5000	Portland Cement	30	TN		
0090	402-3113	Recycled Asphaltic Concrete 12.5 mm Superpave, Gp 1 or 2, Incl Bitum Matl & H Lime	115	TN		
0095	413-1000	Bituminous Tack Coat	80	GAL		
0100	653-1704	Thermoplastic Solid Traffic Stripe, 24 in, White	18	LF		
0110	706-1003	Turf Establishment, TP C	0.07	AC		

Walnut Street from Bell Avenue to Broad Street

0115	301-2160	Soil-Cem Stab Base Crs, 8 in	815	SY		
0120	301-5000	Portland Cement	30	TN		
0125	402-3113	Recycled Asphaltic Concrete 12.5 mm Superpave, Gp 1 or 2, Incl Bitum Matl & H Lime	95	TN		
0130	413-1000	Bituminous Tack Coat	70	GAL		
0135	653-1704	Thermoplastic Solid Traffic Stripe, 24 in, White	16	LF		
0140	706-1003	Turf Establishment, TP C	0.07	AC		

City Cemetery Drives

0145		Asphalt Patching – Full Depth	3	EA		
0150		Asphalt-Rubber Joint and Crack Seal, Type "S"	300	LF		
0155		Coal Tar Emulsion Seal Coat	2,720	SY		

BASE BID TOTAL:

TOTAL PRICE OF PROJECT NOT TO EXCEED: \$ _____

Respectfully Submitted: Signature of Principal: _____

Title: _____

Corporate Seal: