

TOWN OF BRASELTON, GEORGIA

CHEMICAL STORAGE AND WELL TREATMENT FACILITY IMPROVEMENTS  
RECEIVED OCTOBER 30, 2014

ITEM NO.	DESCRIPTION	UNIT	Est. No. of Units	Allsouth Constructors, Inc. 9124 N. Park Drive Covington, GA 30014 770-788-8703		Griffin Bros., Inc. 103 Griffin Drive Maysville, GA 30558 706-484-1922		Sol Construction, LLC 4120 Presidential Pkwy., Ste. 115 Atlanta, GA 30340 770-455-1822		Lanier Contracting Co. 3690 Lawrenceville Suwanee Rd. Suwanee, GA 30024 770-932-1800	
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
02200.00	SITE CLEARING AND GRADING - INCLUDES REMOVAL AND/OR FOUNDATION AND DIRECTING STORMWATER AS SHOWN ON PLAN SHEET C1 AND REMOVAL OF SWEETGUM TREE BRANCH HANGING OVER EX. BLDG.	LS	1	\$3,000.00	\$3,000.00	\$5,500.00	\$5,500.00	\$4,000.00	\$4,000.00	\$2,395.00	\$2,395.00
02270.00	EROSION CONTROL-INCLUDES SILT FENCE, MULCHING INSTALLATION AND MAINTENANCE OF ALL DISTURBED AREAS AS SHOWN ON PLAN SHEET EC1.	LS	1	\$1,000.00	\$1,000.00	\$1,200.00	\$1,200.00	\$2,000.00	\$2,000.00	\$2,400.00	\$2,400.00
Item A	NEW CHEMICAL BULK STORAGE BUILDING-COMPLETE; INCLUDES CONCRETE FOUNDATION, CMU WALLS, ROOF, DOORS, VENTILATION EQUIPMENT, INTERIOR PIPING, ETC.	LS	1	\$74,216.00	\$74,216.00	\$76,239.00	\$76,239.00	\$76,000.00	\$76,000.00	\$115,522.00	\$115,522.00
Item B	CHEMICAL TRANSFER PIPING OUTSIDE OF BUILDINGS--INCLUDES, CLEARING, INSTALLATION OF SCH. 80 PVC PIPING, CORING OF EXISTING BUILDING TO ACCEPT CHEMICAL PIPING, ETC.	LS	1	\$4,000.00	\$4,000.00	\$5,800.00	\$5,800.00	\$9,000.00	\$9,000.00	\$14,700.00	\$14,700.00
Item C	NEW SODIUM HYDROXIDE FEED SYSTEM-INCLUDES DAY TANK, SKID MOUNTED CHEMICAL FEED SYSTEM WITH PUMPS, PIPING AND ACCESSORIES TO CONNECT IT TO EX. CHEMICAL PIPING.	LS	1	\$20,000.00	\$20,000.00	\$22,400.00	\$22,400.00	\$22,000.00	\$22,000.00	\$19,210.00	\$19,210.00
Item D	NEW SODIUM HYPOCHLORINE FEED SYSTEM-INCLUDES SOLUTION DAY TANK, SKID MOUNTED CHEMICAL FEED SYSTEM WITH PUMPS, PIPING AND ACCESSORIES TO CONNECT IT TO EXISTING SYSTEM.	LS	1	\$10,000.00	\$10,000.00	\$9,600.00	\$9,600.00	\$13,000.00	\$13,000.00	\$8,231.00	\$8,231.00
Item E	EXISTING TREATMENT BLDG. MODIFICATIONS-INCLUDES MOFIFICATION OF EXISTING INTERIOR PIPING, INSTALLATION OF NEW INTERIOR CHEMICAL PIPING, ALL CONNECTIONS TO NEW CHEMICAL FEED SYSTEMS, BOLT REPLACEMENT, PAINTING, ETC. AS DESCRIBED ON SHEET C2 OF THE PLANS.	LS	1	\$10,000.00	\$10,000.00	\$6,200.00	\$6,200.00	\$9,000.00	\$9,000.00	\$3,340.00	\$3,340.00
02523.00	GRAVEL DRIVEWAY RESTORATION-PER DETAIL GP8, SHEET D2	LS	1	\$1,000.00	\$1,000.00	\$2,500.00	\$2,500.00	\$10,000.00	\$10,000.00	\$3,660.00	\$3,660.00
16000.00	ELECTRICAL WORK	LS	1	\$15,000.00	\$15,000.00	\$14,000.00	\$14,000.00	\$10,000.00	\$10,000.00	\$13,970.00	\$13,970.00
<b>TOTAL BASE BID</b>					\$138,216.00	\$143,439.00	\$155,000.00	\$183,428.00			

CHEMICAL STORAGE AND WELL TREATMENT FACILITY IMPROVEMENTS  
RECEIVED OCTOBER 30, 2014

ITEM NO.	DESCRIPTION	UNIT	Est. No. of Units	Willow Construction, Inc. 3970 Flint Hill Road Powder Springs, GA 30127-2809 770-222-1555	
				UNIT PRICE	TOTAL FOR ITEM
02200.00	SITE CLEARING AND GRADING - INCLUDES REMOVAL AND/OR FOUNDATION AND DIRECTING STORMWATER AS SHOWN ON PLAN SHEET C1 AND REMOVAL OF SWEETGUM TREE BRANCH HANGING OVER EX. BLDG.	LS	1	\$2,000.00	\$2,000.00
02270.00	EROSION CONTROL-INCLUDES SILT FENCE, MULCHING INSTALLATION AND MAINTENANCE OF ALL DISTURBED AREAS AS SHOWN ON PLAN SHEET EC1.	LS	1	\$1,500.00	\$1,500.00
Item A	NEW CHEMICAL BULK STORAGE BUILDING-COMPLETE; INCLUDES CONCRETE FOUNDATION, CMU WALLS, ROOF, DOORS, VENTILATION EQUIPMENT, INTERIOR PIPING, ETC.	LS	1	\$121,200.00	\$121,200.00
Item B	CHEMICAL TRANSFER PIPING OUTSIDE OF BUILDINGS--INCLUDES, CLEARING, INSTALLATION OF SCH. 80 PVC PIPING, CORING OF EXISTING BUILDING TO ACCEPT CHEMICAL PIPING, ETC.	LS	1	\$6,000.00	\$6,000.00
Item C	NEW SODIUM HYDROXIDE FEED SYSTEM-INCLUDES DAY TANK, SKID MOUNTED CHEMICAL FEED SYSTEM WITH PUMPS, PIPING AND ACCESSORIES TO CONNECT IT TO EX. CHEMICAL PIPING.	LS	1	\$30,000.00	\$30,000.00
Item D	NEW SODIUM HYPOCHLORINE FEED SYSTEM-INCLUDES SOLUTION DAY TANK, SKID MOUNTED CHEMICAL FEED SYSTEM WITH PUMPS, PIPING AND ACCESSORIES TO CONNECT IT TO EXISTING SYSTEM.	LS	1	\$15,000.00	\$15,000.00
Item E	EXISTING TREATMENT BLDG. MODIFICATIONS-INCLUDES MODIFICATION OF EXISTING INTERIOR PIPING, INSTALLATION OF NEW INTERIOR CHEMICAL PIPING, ALL CONNECTIONS TO NEW CHEMICAL FEED SYSTEMS, BOLT REPLACEMENT, PAINTING, ETC. AS DESCRIBED ON SHEET C2 OF THE PLANS.	LS	1	\$6,000.00	\$6,000.00
02523.00	GRAVEL DRIVEWAY RESTORATION-PER DETAIL GP8, SHEET D2	LS	1	\$7,000.00	\$7,000.00
16000.00	ELECTRICAL WORK	LS	1	\$11,000.00	\$11,000.00
<b>TOTAL BASE BID</b>					<b>\$199,700.00</b>

**TOTAL BID FOR THE CHEMICAL STORAGE AND WELL TREATMENT FACILITY IMPROVEMENTS:**

I hereby certify this to be a true and accurate tabulation of bids received by the Town of Braselton, Georgia on October 30, 2014 at 2:00 p.m.

Kelby Hobbs

Engineering Management, Inc.

