

**Town of Braselton
Mulberry River Interceptor Sewer
Jackson County, Georgia**

Services Provided:

Design and Permitting
Easement Acquisition
Bid Phase Management
Construction Observation
Interagency Coordination
GA DNR
GA EPD
Army Corps of Engineers
Hall County
Gwinnett County
Jackson County
Barrow County

Project Data:

Phase I
Total Project Cost:
\$1.8 Million

Completion Date:
2005

Phase II
Total Project Cost:
\$5.4 Million

Estimated Completion
Date: 2015

Contact:

Ms. Jennifer Dees
Town Manager
Town of Braselton
P.O. Box 306
Braselton, GA 30517
(706) 654-3915



During the past decade, the Town of Braselton has experienced unprecedented residential, commercial and Industrial growth. The Town's service area spans four Counties with the Mulberry River being the major drainage basin. This basin provides a central, accessible collection route to a very large portion of the current and future growth. Engineering Management, Inc. (EMI) provided a comprehensive study of the basin including projections of future land use, waste water flow projections and routing and sizing of interceptor and collection sewer lines, as well as pumping facilities. Portions of the project were undertaken utilizing a design-build approach with EMI providing services as program managers.

Remaining portions of the project have been completed utilizing the design-bid-build method, with a third phase currently ready to proceed to the bid phase. The entire project consists of 12 miles of 12" to 36" sewer lines and 2 waste water pumping facilities of 1,500 and 6,000 GPM capacity.

Portions of the Mulberry River sewer corridor were adapted to include a nature trail with amenities extending from Liberty Church Road north to the Hall County line.