

CITY OF HOSCHTON, GEORGIA
SEWER SYSTEM EXPANSION TO THE SOUTH INDUSTRIAL PARK
APRIL 10, 2019

ITEM NO.	DESCRIPTION	UNIT	No. of Units	J&K Utilities, LLC		Griffin Bros., Inc.		Mid-South Builders, Inc.	
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
						1085 Winder Hwy/P.O. Box 35 Jefferson, GA 30549 (706) 367-9464	103 Griffin Drive Maysville, GA 30558 (706) 677-3549	7057 Maddox Rd./P.O. Box 878 Lithonia, GA 30058 (770) 484-9600	
01025.00	VIDEO TAPING OF THE PIPELINE ROUTES AND PUMP STATION SITE	LS	1	\$500.00	\$500.00				
02270.01	ROCK REMOVAL - TRENCH ROCK	CY	450	\$70.00	\$31,500.00				
02270.00	EROSION CONTROL								
02270.01	SILT FENCE - TYPE A	LF	1,400	\$2.60	\$3,640.00	\$1.81	\$2,534.00	\$1.50	\$2,100.00
02270.02	SILT FENCE - TYPE C	LF	200	\$3.30	\$660.00	\$2.87	\$574.00	\$3.50	\$700.00
02270.03	HAYBALE CHECKDAMS	EA	10	\$60.00	\$600.00	\$36.00	\$360.00	\$120.00	\$1,200.00
02270.04	CONSTRUCTION EXIT	EA	1	\$2,800.00	\$2,800.00	\$1,685.64	\$1,685.64	\$2,500.00	\$2,500.00
02272.00	RIP RAP	CY	80	\$80.00	\$6,400.00	\$51.63	\$4,130.40	\$1.00	\$80.00
02300.00	BORING AND JACKING								
02300.01	JACK AND BORE CONVENTIONAL - COMPLETE WITH 16" STEEL CASING AND 8" CLASS 350 DIP GRAVITY SEWER, RESTRAINED JOINTS AND PROTECTO 401 COATING	LF	70	\$260.00	\$18,200.00	\$358.70	\$25,109.00	\$400.00	\$28,000.00
02300.02	COMPLETE WITH 16" STEEL CASING AND 8" CLASS 350 DIP GRAVITY SEWER, RESTRAINED JOINTS AND PROTECTO 401 COATING	LF	20	\$340.00	\$6,800.00	\$793.70	\$15,874.00	\$1.00	\$20.00
02300.03	JACK AND BORE - COMPLETE WITH 12" STEEL CASING AND 6" SDR 35 PVC GRAVITY SEWER	LF	28	\$235.00	\$6,580.00	\$309.08	\$8,654.24	\$300.00	\$8,400.00
02300.04	COMPLETE WITH 12" STEEL CASING AND 6" SDR 35 PVC GRAVITY SEWER	LF	10	\$260.00	\$2,600.00	\$344.08	\$3,440.80	\$1.00	\$10.00
02510.00	ASPHALT PAVEMENT REPLACEMENT - SHEET PV								
02510.01	REMOVE EXISTING ASPHALT	SY	4,040	\$3.25	\$13,130.00	\$8.50	\$34,340.00	\$5.50	\$22,220.00
02510.02	UNCLASSIFIED EXCAVATION REQUIRED FOR PLACEMENT OF 8" GAB	CY	898	\$22.00	\$19,756.00	\$20.00	\$17,960.00	\$45.00	\$40,410.00
02510.03	REPAIR OF SOFT SUB-BASE - COMPLETE INCLUDING EXCAVATION OF UNACCEPTABLE MATERIAL AND REPAIR WITH GAB	CY	100	\$53.50	\$5,350.00	\$42.27	\$4,227.00	\$85.00	\$8,500.00
02510.04	INSTALLATION OF GEOTEXTILE FABRIC IN SOFT SUB-BASE REPAIR AREAS - COMPLETE INCLUDING MATERIALS, LABOR, ETC.	SY	300	\$1.25	\$375.00	\$2.00	\$600.00	\$5.00	\$1,500.00
02510.05	8" GAB ROAD BASE	SY	4,040	\$13.75	\$55,550.00	\$20.74	\$83,789.60	\$20.00	\$80,800.00
02510.06	4" 19MM SUPERPAVE ASPHALT BINDER INCLUDING BITUMINOUS PRIME	TON	890	\$97.00	\$86,330.00	\$108.09	\$96,200.10	\$140.00	\$124,600.00
02510.07	2" 12.5MM SUPERPAVE ASPHALT WEAR SURFACE	TON	445	\$103.00	\$45,835.00	\$119.10	\$52,999.50	\$145.00	\$64,525.00
02510.08	BITUMINOUS TACK COAT	GAL	404	\$4.00	\$1,616.00	\$5.25	\$2,121.00	\$5.00	\$2,020.00

CITY OF HOSCHTON, GEORGIA
SEWER SYSTEM EXPANSION TO THE SOUTH INDUSTRIAL PARK
APRIL 10, 2019

02575.00	DRIVEWAY REPAIR / INSTALLATION								
02575.01	GRAVEL DRIVEWAY REPAIR	LF	36	\$83.00	\$2,988.00	\$9.72	\$349.92	\$15.00	\$540.00
02575.02	TEMPORARY GRAVEL DETOUR LANE INSTALLATION AND REMOVAL UPON PROJECT COMPLETION	SY	530	\$13.75	\$7,287.50	\$9.31	\$4,934.30	\$15.00	\$7,950.00
02575.03	ASPHALT PAVEMENT CUT AND REPAIR	LF	675	\$38.00	\$25,650.00	\$64.57	\$43,584.75	\$50.00	\$33,750.00
02575.04	CONCRETE CURB AND GUTTER CUT AND REPAIR	LF	20	\$30.00	\$600.00	\$60.00	\$1,200.00	\$40.00	\$800.00
02601.00	MANHOLES								
02601.01	STANDARD 4'-0" MANHOLE INCLUDES BASE, CONE, RISER, FRAME AND COVER, COMPLETE, 0'-6' DEPTH	EA	13	\$3,295.00	\$42,835.00	\$3,106.72	\$40,387.36	\$3,350.00	\$43,550.00
02601.02	4'-0" MANHOLE ADDITIONAL VERTICAL FEET	VF	80	\$400.00	\$32,000.00	\$190.72	\$15,257.60	\$150.00	\$12,000.00
02602.00	EXISTING MANHOLE / WETWELL COATINGS								
02602.01	COATING EXISTING 4'-0" MANHOLE C1	EA	1	\$2,160.00	\$2,160.00	\$1,076.91	\$1,076.91	\$3,000.00	\$3,000.00
02603.00	NEW MANHOLE / WETWELL COATINGS								
02603.01	COATING NEW 8'-0" DIAMETER WETWELL	EA	1	\$10,580.00	\$10,580.00	\$6,875.81	\$6,875.81	\$16,000.00	\$16,000.00
02603.02	COATING NEW 4'-0" DIAMETER MANHOLE A1	EA	1	\$3,160.00	\$3,160.00	\$2,500.00	\$2,500.00	\$5,000.00	\$5,000.00
02732.00	SANITARY SEWER FORCE MAINS								
02732.01	6" DR 18 C900 PVC FORCE MAIN	LF	1,650	\$16.50	\$27,225.00	\$30.84	\$50,886.00	\$31.06	\$51,249.00
02732.02	COMBO SEWAGE AIR/VACUUM AIR RELEASE VALVE AND MANHOLE - COMPLETE	EA	2	\$7,500.00	\$15,000.00	\$6,930.21	\$13,860.42	\$10,000.00	\$20,000.00
02732.03	CORE AND CONNECT NEW 6" FORCEMAIN TO EXISTING MANHOLE C1 - COMPLETE	EA	1	\$2,800.00	\$2,800.00	\$1,550.00	\$1,550.00	\$1,500.00	\$1,500.00
02736.00	SANITARY SEWER								
02736.01	8" DIA. SDR 35 PVC, 6-8' CUT	LF	98	\$45.00	\$4,410.00	\$58.14	\$5,697.72	\$120.00	\$11,760.00
02736.02	8" DIA. SDR 35 PVC, 8-10' CUT	LF	1,042	\$46.50	\$48,453.00	\$63.14	\$65,791.88	\$123.00	\$128,166.00
02736.03	8" DIA. SDR 35 PVC, 10-12' CUT	LF	343	\$51.60	\$17,698.80	\$68.14	\$23,372.02	\$131.00	\$44,933.00
02736.04	8" DIA. SDR 35 PVC, 12-14' CUT	LF	462	\$54.00	\$24,948.00	\$73.14	\$33,790.68	\$134.00	\$61,908.00
02736.05	8" DIA. SDR 35 PVC, 14-16' CUT	LF	76	\$56.00	\$4,256.00	\$88.14	\$6,698.64	\$137.00	\$10,412.00
02736.06	8" DIA. SDR 35 PVC, 16-18' CUT	LF	201	\$59.00	\$11,859.00	\$108.14	\$21,736.14	\$139.00	\$27,939.00
02736.07	8" DIA. SDR 35 PVC, 18-20' CUT	LF	232	\$62.00	\$14,384.00	\$128.14	\$29,728.48	\$142.00	\$32,944.00
02736.08	8" DIA. CLASS 350 DIP WITH RESTRAINED JOINTS AND PROTECTO 401 COATING, ALL DEPTHS	LF	20	\$125.00	\$2,500.00	\$155.86	\$3,117.20	\$160.00	\$3,200.00
02736.09	±220 LF 6" DIA. SDR 35 PVC SERVICE LATERAL, INCLUDING CLEANOUTS - COMPLETE	LS	1	\$7,150.00	\$7,150.00	\$9,445.55	\$9,445.55	\$16,500.00	\$16,500.00
02736.10	6" DIA. SDR 35 PVC STUBOUT WITH CLEANOUT - COMPLETE	EA	12	\$1,250.00	\$15,000.00	\$3,027.64	\$36,331.68	\$1,200.00	\$14,400.00
02931.00	PERMANENT GRASSING	LF	2,500	\$2.50	\$6,250.00	\$1.50	\$3,750.00	\$1.50	\$3,750.00
11310.01	SUBMERSIBLE SEWAGE PUMP STATION								
11310.01	SOUTH INDUSTRIAL PARK SUBMERSIBLE LIFT STATION - COMPLETE	LS	1	\$388,220.00	\$388,220.00	\$359,967.45	\$359,967.45	\$354,726.00	\$354,726.00
TOTAL BASE BID					\$1,025,636.30		\$1,168,489.79		\$1,325,562.00

CITY OF HOSCHTON, GEORGIA
SEWER SYSTEM EXPANSION TO THE SOUTH INDUSTRIAL PARK
APRIL 10, 2019

MANDATORY ALTERNATE BID ITEMS

ITEM NO.	DESCRIPTION	UNIT	No. of Units	J&K Utilities, LLC		Griffin Bros., Inc.		Mid-South Builders, Inc.	
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
02736.01A	8" DIA. SDR 26 PVC, 6-8' CUT	LF	98	\$47.25	\$4,630.50	\$59.41	\$5,822.18	\$121.50	\$11,907.00
02736.02A	8" DIA. SDR 26 PVC, 8-10' CUT	LF	1,042	\$48.75	\$50,797.50	\$64.41	\$67,115.22	\$124.50	\$129,729.00
02736.03A	8" DIA. SDR 26 PVC, 10-12' CUT	LF	343	\$53.85	\$18,470.55	\$69.41	\$23,807.63	\$132.50	\$45,447.50
02736.04A	8" DIA. SDR 26 PVC, 12-14' CUT	LF	462	\$56.25	\$25,987.50	\$74.41	\$34,377.42	\$135.50	\$62,601.00
02736.05A	8" DIA. SDR 26 PVC, 14-16' CUT	LF	76	\$58.25	\$4,427.00	\$89.41	\$6,795.16	\$138.50	\$10,526.00
02736.06A	8" DIA. SDR 26 PVC, 16-18' CUT	LF	201	\$61.25	\$12,311.25	\$109.41	\$21,991.41	\$140.50	\$28,240.50
02736.07A	8" DIA. SDR 26 PVC, 18-20' CUT	LF	232	\$64.25	\$14,906.00	\$129.41	\$30,023.12	\$143.50	\$33,292.00
NPDES	NPDES, EROSION, SEDIMENTATION	LS	1	\$4,500.00	\$4,500.00	\$4,400.00	\$4,400.00	\$5,000.00	\$5,000.00

CITY OF HOSCHTON, GEORGIA
SEWER SYSTEM EXPANSION TO THE SOUTH INDUSTRIAL PARK
APRIL 10, 2019

ITEM NO.	DESCRIPTION	UNIT	No. of Units	Wilcorp, Inc.		The Dickerson Group, Inc.		G.P.'s Enterprises, Inc.	
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
				215 Coats Drive Toccoa, GA 30577 (706) 886-0077		871 Old Peachtree Road NW Lawrenceville, GA 30043 (770) 513-4588		1500 Hwy 124 Auburn, GA (770) 945-0810	
01025.00	VIDEO TAPING OF THE PIPELINE ROUTES AND PUMP STATION SITE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00
02270.01	ROCK REMOVAL - TRENCH ROCK	CY	450	\$70.00	\$31,500.00	\$70.00	\$31,500.00	\$70.00	\$31,500.00
02270.00	EROSION CONTROL								
02270.01	SILT FENCE - TYPE A	LF	1,400	\$5.00	\$7,000.00	\$4.00	\$5,600.00	\$4.56	\$6,384.00
02270.02	SILT FENCE - TYPE C	LF	200	\$8.00	\$1,600.00	\$4.00	\$800.00	\$10.42	\$2,084.00
02270.03	HAYBALE CHECKDAMS	EA	10	\$500.00	\$5,000.00	\$15.00	\$150.00	\$488.46	\$4,884.60
02270.04	CONSTRUCTION EXIT	EA	1	\$4,000.00	\$4,000.00	\$2,500.00	\$2,500.00	\$3,200.00	\$3,200.00
02272.00	RIP RAP	CY	80	\$150.00	\$12,000.00	\$55.00	\$4,400.00	\$97.69	\$7,815.20
02300.00	BORING AND JACKING								
02300.01	JACK AND BORE CONVENTIONAL - COMPLETE WITH 16" STEEL CASING AND 8" CLASS 350 DIP GRAVITY SEWER, RESTRAINED JOINTS AND PROTECTO 401 COATING	LF	70	\$375.00	\$26,250.00	\$632.00	\$44,240.00	\$488.46	\$34,192.20
02300.02	ADD ON CHARGE - JACK AND BORE THROUGH ROCK - COMPLETE WITH 16" STEEL CASING AND 8" CLASS 350 DIP GRAVITY SEWER, RESTRAINED JOINTS AND PROTECTO 401 COATING	LF	20	\$1,200.00	\$24,000.00	\$675.00	\$13,500.00	\$716.41	\$14,328.20
02300.03	JACK AND BORE - COMPLETE WITH 12" STEEL CASING AND 6" SDR 35 PVC GRAVITY SEWER	LF	28	\$375.00	\$10,500.00	\$598.00	\$16,744.00	\$358.21	\$10,029.88
02300.04	ADD ON CHARGE - JACK AND BORE THROUGH ROCK- COMPLETE WITH 12" STEEL CASING AND 6" SDR 35 PVC GRAVITY SEWER	LF	10	\$1,200.00	\$12,000.00	\$675.00	\$6,750.00	\$618.72	\$6,187.20
02510.00	ASPHALT PAVEMENT REPLACEMENT - SHEET PV								
02510.01	REMOVE EXISTING ASPHALT	SY	4,040	\$6.00	\$24,240.00	\$10.10	\$40,804.00	\$15.63	\$63,145.20
02510.02	UNCLASSIFIED EXCAVATION REQUIRED FOR PLACEMENT OF 8" GAB	CY	898	\$50.00	\$44,900.00	\$30.00	\$26,940.00	\$30.65	\$27,523.70
02510.03	REPAIR OF SOFT SUB-BASE - COMPLETE INCLUDING EXCAVATION OF UNACCEPTABLE MATERIAL AND REPAIR WITH GAB	CY	100	\$75.00	\$7,500.00	\$38.00	\$3,800.00	\$91.64	\$9,164.00
02510.04	INSTALLATION OF GEOTEXTILE FABRIC IN SOFT SUB-BASE REPAIR AREAS - COMPLETE INCLUDING MATERIALS, LABOR, ETC.	SY	300	\$7.00	\$2,100.00	\$2.00	\$600.00	\$29.21	\$8,763.00
02510.05	8" GAB ROAD BASE	SY	4,040	\$28.00	\$113,120.00	\$19.25	\$77,770.00	\$20.87	\$84,314.80
02510.06	4" 19MM SUPERPAVE ASPHALT BINDER INCLUDING BITUMINOUS PRIME	TON	890	\$127.00	\$113,030.00	\$150.00	\$133,500.00	\$254.00	\$226,060.00
02510.07	2" 12.5MM SUPERPAVE ASPHALT WEAR SURFACE	TON	445	\$135.00	\$60,075.00	\$150.00	\$66,750.00	\$273.54	\$121,725.30
02510.08	BITUMINOUS TACK COAT	GAL	404	\$15.00	\$6,060.00	\$10.00	\$4,040.00	\$10.42	\$4,209.68

CITY OF HOSCHTON, GEORGIA
SEWER SYSTEM EXPANSION TO THE SOUTH INDUSTRIAL PARK
APRIL 10, 2019

02575.00	DRIVEWAY REPAIR / INSTALLATION								
02575.01	GRAVEL DRIVEWAY REPAIR	LF	36	\$150.00	\$5,400.00	\$12.00	\$432.00	\$110.61	\$3,981.96
02575.02	TEMPORARY GRAVEL DETOUR LANE INSTALLATION AND REMOVAL UPON PROJECT COMPLETION	SY	530	\$38.00	\$20,140.00	\$15.00	\$7,950.00	\$38.66	\$20,489.80
02575.03	ASPHALT PAVEMENT CUT AND REPAIR	LF	675	\$10.00	\$6,750.00	\$72.00	\$48,600.00	\$54.50	\$36,787.50
02575.04	CONCRETE CURB AND GUTTER CUT AND REPAIR	LF	20	\$100.00	\$2,000.00	\$30.00	\$600.00	\$71.64	\$1,432.80
02601.00	MANHOLES								
02601.01	STANDARD 4'-0" MANHOLE INCLUDES BASE, CONE, RISER, FRAME AND COVER, COMPLETE, 0'-6' DEPTH	EA	13	\$8,000.00	\$104,000.00	\$4,800.00	\$62,400.00	\$4,247.13	\$55,212.69
02601.02	4'-0" MANHOLE ADDITIONAL VERTICAL FEET	VF	80	\$1,000.00	\$80,000.00	\$3,200.00	\$256,000.00	\$400.00	\$32,000.00
02602.00	EXISTING MANHOLE / WETWELL COATINGS								
02602.01	COATING EXISTING 4'-0" MANHOLE C1	EA	1	\$10,000.00	\$10,000.00	\$3,110.00	\$3,110.00	\$18,782.05	\$18,782.05
02603.00	NEW MANHOLE / WETWELL COATINGS								
02603.01	COATING NEW 8'-0" DIAMETER WETWELL	EA	1	\$25,000.00	\$25,000.00	\$9,875.00	\$9,875.00	\$22,038.25	\$22,038.25
02603.02	COATING NEW 4'-0" DIAMETER MANHOLE A1	EA	1	\$10,000.00	\$10,000.00	\$5,022.00	\$5,022.00	\$16,176.00	\$16,176.00
02732.00	SANITARY SEWER FORCE MAINS								
02732.01	6" DR 18 C900 PVC FORCE MAIN	LF	1,650	\$32.00	\$52,800.00	\$80.00	\$132,000.00	\$55.59	\$91,723.50
02732.02	COMBO SEWAGE AIR/VACUUM AIR RELEASE VALVE AND MANHOLE - COMPLETE	EA	2	\$13,000.00	\$26,000.00	\$11,250.00	\$22,500.00	\$13,857.43	\$27,714.86
02732.03	CORE AND CONNECT NEW 6" FORCEMAIN TO EXISTING MANHOLE C1 - COMPLETE	EA	1	\$6,500.00	\$6,500.00	\$6,120.00	\$6,120.00	\$4,756.41	\$4,756.41
02736.00	SANITARY SEWER								
02736.01	8" DIA. SDR 35 PVC, 6-8' CUT	LF	98	\$56.00	\$5,488.00	\$85.00	\$8,330.00	\$66.62	\$6,528.76
02736.02	8" DIA. SDR 35 PVC, 8-10' CUT	LF	1,042	\$66.00	\$68,772.00	\$85.00	\$88,570.00	\$77.84	\$81,109.28
02736.03	8" DIA. SDR 35 PVC, 10-12' CUT	LF	343	\$76.00	\$26,068.00	\$85.00	\$29,155.00	\$90.67	\$31,099.81
02736.04	8" DIA. SDR 35 PVC, 12-14' CUT	LF	462	\$86.00	\$39,732.00	\$92.00	\$42,504.00	\$97.20	\$44,906.40
02736.05	8" DIA. SDR 35 PVC, 14-16' CUT	LF	76	\$96.00	\$7,296.00	\$94.50	\$7,182.00	\$110.31	\$8,383.56
02736.06	8" DIA. SDR 35 PVC, 16-18' CUT	LF	201	\$106.00	\$21,306.00	\$108.00	\$21,708.00	\$114.10	\$22,934.10
02736.07	8" DIA. SDR 35 PVC, 18-20' CUT	LF	232	\$116.00	\$26,912.00	\$115.00	\$26,680.00	\$120.31	\$27,911.92
02736.08	8" DIA. CLASS 350 DIP WITH RESTRAINED JOINTS AND PROTECTO 401 COATING, ALL DEPTHS	LF	20	\$80.00	\$1,600.00	\$125.00	\$2,500.00	\$414.00	\$8,280.00
02736.09	±220 LF 6" DIA. SDR 35 PVC SERVICE LATERAL, INCLUDING CLEANOUTS - COMPLETE	LS	1	\$12,500.00	\$12,500.00	\$41,500.00	\$41,500.00	\$15,071.15	\$15,071.15
02736.10	6" DIA. SDR 35 PVC STUBOUT WITH CLEANOUT - COMPLETE	EA	12	\$5,500.00	\$66,000.00	\$955.00	\$11,460.00	\$1,592.31	\$19,107.72
02931.00	PERMANENT GRASSING								
11310.01	SOUTH INDUSTRIAL PARK SUBMERSIBLE LIFT STATION - COMPLETE	LS	1	\$288,000.00	\$288,000.00	\$415,000.00	\$415,000.00	\$976,922.74	\$976,922.74
TOTAL BASE BID					\$1,442,639.00		\$1,742,586.00		\$2,278,437.22

CITY OF HOSCHTON, GEORGIA
SEWER SYSTEM EXPANSION TO THE SOUTH INDUSTRIAL PARK
APRIL 10, 2019

MANDATORY ALTERNATE BID ITEMS

ITEM NO.	DESCRIPTION	UNIT	No. of Units	Wilcorp, Inc. 215 Coats Drive Toccoa, GA 30577 (706) 886-0077		The Dickerson Group, Inc. 871 Old Peachtree Road NW Lawrenceville, GA 30043 (770) 513-4588		G.P.'s Enterprises, Inc. 1500 Hwy 124 Auburn, GA (770) 945-0810	
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
02736.01A	8" DIA. SDR 26 PVC, 6-8' CUT	LF	98	\$58.00	\$5,684.00	\$84.00	\$8,232.00	\$70.62	\$6,920.76
02736.02A	8" DIA. SDR 26 PVC, 8-10' CUT	LF	1,042	\$68.00	\$70,856.00	\$84.00	\$87,528.00	\$81.84	\$85,277.28
02736.03A	8" DIA. SDR 26 PVC, 10-12' CUT	LF	343	\$78.00	\$26,754.00	\$84.00	\$28,812.00	\$94.67	\$32,471.81
02736.04A	8" DIA. SDR 26 PVC, 12-14' CUT	LF	462	\$88.00	\$40,656.00	\$90.80	\$41,949.60	\$101.20	\$46,754.40
02736.05A	8" DIA. SDR 26 PVC, 14-16' CUT	LF	76	\$98.00	\$7,448.00	\$93.50	\$7,106.00	\$114.31	\$8,687.56
02736.06A	8" DIA. SDR 26 PVC, 16-18' CUT	LF	201	\$108.00	\$21,708.00	\$107.00	\$21,507.00	\$118.10	\$23,738.10
02736.07A	8" DIA. SDR 26 PVC, 18-20' CUT	LF	232	\$118.00	\$27,376.00	\$114.00	\$26,448.00	\$124.31	\$28,839.92
NPDES	NPDES, EROSION, SEDIMENTATION	LS	1	\$15,000.00	\$15,000.00	\$8,500.00	\$8,500.00	\$8,500.00	\$8,500.00

I hereby certify this to be a true and accurate tabulation of bids received by the City of Hoschton on April 10, 2019.

Greg Bennett, PE
 Engineering Management, Inc.


