

**STORMWATER DRAINAGE IMPROVEMENTS  
FOR THE  
CITY OF HELEN, GEORGIA**

**RECEIVED AUGUST 20, 2013**

ITEM NO.	DESCRIPTION	UNIT	Est. No. of Units	Square Deal Ent., Inc. 310 Welcome Lane Satee, GA 30571 706-318-9876		Dodd Construction 148 Chapplean Road Lavonia, GA 30553 706-356-0708		UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM				
1	VIDEO TAPING THE PROJECT SITE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00				
2	ROCK REMOVAL	CY	100	\$60.00	\$6,000.00	\$60.00	\$6,000.00				
3	18-INCH SMOOTH LINED PLASTIC CULVERT - INSTALLED	LF	1,338	\$27.16	<b>\$36,340.08</b>	\$35.00	\$46,830.00				
4	24-INCH SMOOTH LINED PLASTIC CULVERT - INSTALLED	LF	349	\$33.83	<b>\$11,806.67</b>	\$50.00	\$17,450.00				
5	PRECAST CONCRETE DOUBLE WING CATCH BASIN PER GDOT STANDARD SPECIFICATION 668-INSTALLED	EA	2	\$1,900.00	\$3,800.00	\$2,000.00	\$4,000.00				
6	PRECAST CONCRETE SINGLE WING CATCH BASIN PER GDOT STANDARD SPECIFICATION 668 - INSTALLED	EA	9	\$1,800.00	\$16,200.00	\$1,500.00	\$13,500.00				
7	PRECAST CONCRETE JUNCTION BOX PER GDOT STANDARD SPECIFICATION 668 - INSTALLED	EA	8	\$1,583.00	\$12,664.00	\$1,500.00	\$12,000.00				
8	PRECAST CONCRETE DROP INLET PER GDOT STANDARD SPECIFICATION 668 - INSTALLED	EA	15	\$1,478.00	\$22,170.00	\$1,200.00	\$18,000.00				
9	ASPHALT PAVEMENT FOR ROADWAY AND PARKING LOT PER GDOT STANDARD SPECIFICATION 400-COMplete	SY	5,827	\$29.00	\$168,983.00	\$25.00	\$145,675.00				
10	CONCRETE CURB & GUTTER PER GDOT STANDARD SPECIFICATION 441-COMplete	LF	4,937	\$10.20	<b>\$50,357.40</b>	\$20.00	\$98,740.00				
11	CONCRETE VALLEY GUTTER PER GDOT STANDARD DETAIL 9031J SHEET D7-COMplete	SY	285	\$37.30	<b>\$10,630.50</b>	\$18.00	\$5,130.00				
12	CONCRETE STAIRCASE PER SHEET D2-COMplete	LS	1	\$5,400.00	\$5,400.00	\$5,200.00	\$5,200.00				
13	PARKING SPACE STRIPING PER GDOT STANDARD SPECIFICATION 652-COMplete	LF	961	\$0.53	<b>\$509.33</b>	\$0.50	\$480.50				
14	CROSSWALK LADDER STRIPING PER GDOT STANDARD SPECIFICATION 652-COMplete	LF	160	\$7.35	\$1,176.00	\$0.50	\$80.00				
15	STOPBAR STRIPING PER GDOT STANDARD SPECIFICATION 652-COMplete	LF	63	\$2.63	<b>\$165.69</b>	\$1.00	\$63.00				
16	DIRECTIONAL ARROWS PER GDOT STANDARD SPECIFICATION 652-COMplete	EA	22	\$36.77	<b>\$808.94</b>	\$100.00	\$2,200.00				
17	5 FOOT WIDE CONCRETE SIDEWALK-COMplete PER SECTION 02575	LF	1,047	\$15.50	<b>\$16,228.50</b>	\$20.00	\$20,940.00				
18	GRADING-COMplete PER SECTION 2000	LS	1	\$49,315.00	\$49,315.00	\$80,000.00	\$80,000.00				
19	SEDIMENT TRAPS	EA	24	\$125.00	\$3,000.00	\$100.00	\$2,400.00				
20	TYPE "C" SILT FENCE	LF	4,893	\$2.25	\$11,009.25	\$2.00	\$9,786.00				
21	CONSTRUCTION EXIT	EA	1	\$1,500.00	\$1,500.00	\$1,000.00	\$1,000.00				
22	GRASSING, COMPLETE INCLUDING SEED, FERTILIZER, MULCH, LIME, ETC.	SY	1,000	\$2.30	\$2,300.00	\$3.00	\$3,000.00				
23	UNSUITABLE SOIL REMOVAL AND REPLACEMENT - COMPLETE	CY	200	\$24.00	\$4,800.00	\$20.00	\$4,000.00				
<b>TOTAL BASE BID</b>					<b>\$435,664.36</b>		<b>\$492,974.50</b>		\$0.00		\$0.00

**STORMWATER DRAINAGE IMPROVEMENTS  
FOR THE  
CITY OF HELEN, GEORGIA**

**MANDATORY ALTERNATE BID ITEMS**

**RECEIVED AUGUST 20, 2013**

ITEM NO.	DESCRIPTION	UNIT	Est. No. of Units								
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
Alt-001	BRICK DOUBLE WING CATCH BASIN FABRICATED IN PLACE-CONSTRUCTION MUST BE IN ACCORDANCE WITH GDOT SPECIFICATION 668 AND GDOT DETAIL 9031U.	EA	2	\$2,280.00	\$4,560.00	\$1,500.00	\$3,000.00				
Alt-002	BRICK SINGLE WING CATCH BASIN FABRICATED IN PLACE-CONSTRUCTION MUST BE IN ACCORDANCE WITH GDOT SPECIFICATION 668 AND GDOT DETAIL 9031U.	EA	9	\$2,160.00	\$19,440.00	\$1,200.00	\$10,800.00				
Alt-003	BRICK JUNCTION BOX FABRICATED IN PLACE--CONSTRUCTION MUST BE IN ACCORDANCE WITH GDOT SPECIFICATION 668 AND GDOT DETAIL 9031U.	LF	10	\$1,900.00	\$19,000.00	\$1,200.00	\$12,000.00				
Alt-004	BRICK DROP INLET FABRICATED IN PLACE-CONSTRUCTION MUST BE IN ACCORDANCE WITH GDOT SPECIFICATION 668 AND GDOT DETAIL 9031U.	EA	13	\$1,774.00	\$23,062.00	\$1,000.00	\$13,000.00				
Alt-005	NPDES, EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN IMPLEMENTATION.	LS	1	\$2,400.00	\$2,400.00	\$3,000.00	\$3,000.00				

**TOTAL BID FOR THE STORMWATER DRAINAGE IMPROVEMENTS:**

**I hereby certify this to be a true and accurate tabulation  
of bids received by the City of Helen, Georgia  
on August 20, 2013 at 2:00 p.m.**

**Fletcher Holliday  
Engineering Management, Inc.**